

www.ConcreteStudioDFW.com
Concrete Flooring

Concrete Studio
Phone: 214/ 321-1575
Email: dave@ConcreteStudioDFW.com

Zinaii. davo godilorotootaalobi viitooli

February 2015

Scheduling Guidelines for Decorative Concrete Floors

The general work phases of a residential or small commercial decorative concrete floor job can be summarized as:

Phase 1 = Score, Clean, Color & Cover Phase 2 = Seal & Finish, Cure Period Below are points in the construction timeline when the work phases of floor prep, scoring, coloring and finishing should ideally be performed. The activities listed under 'structure' are not meant to be complete or perfectly ordered but only to provide builders & contractors with a general idea of the activities timeline. (Note: job day = \sim 2,000 sq. ft.)

STRUCTURE:	Site work	&	pre-pour	plumbing, etc.	

Slab poured

FLOOR: Scoring (if done prior to framing)

] <u>Duration:</u> $\sim 2,000 - 3,000 \text{ sf/d}$, as

Duration: $\sim 2,000 - 3,000 \text{ sf/d}$,

longer for multi-color and/or

soon as pour +1.

<u>STRUCTURE:</u> Framing; electrical; plumbing, etc.

STRUCTURE: Drywall installed

Insulation

Tape & bed; texture

FLOOR: Phase One:

Scoring (if done after framing)

Clean concrete Stain/Color concrete

Stain/Color concrete] high degree-of-difficulty Cover concrete edge-to-edge] scoring or coloring.

STRUCTURE: Set cabinets & built-ins (over covered concrete)

Install trim (directly over covered concrete)

STRUCTURE: Interior finish-out - all painting & other finish work

Plumbing fixtures & all appliances installed

All other floor coverings, carpet, wood, etc. installed

Electrical & Plumbing finish-out completed

FLOOR: Phase Two:

Uncover & re-clean concrete

Seal concrete Finish concrete

Cure period (48 – 72 hours)

<u>Duration:</u> ~ 2 days per 5,000 sf
 plus 24 hr. initial dry time for light
 foot traffic, longer for specialty

] coatings & finishes.

STRUCTURE: Paint touch-up, final cleaning, punch